

**VILLAGE CHURCH**

*Congregational • United Church of Christ*

---

*Wellesley + Weston*

**EMPOWERING  
THE FUTURE**



# Chronology to geothermal decision

- **2014 capital campaign:** allotted \$400K for environmental stewardship
- **2014 – 2021 research & projects:** Sealed the building envelope, partial lighting conversion, solar array, preparations for HVAC replacement.
- **2022 HVAC design:** HVAC at end of useful life. Preliminary geothermal high-level design and estimate completed (\$70K cost for design).
- **2022 – 2023: decision process (part 1 – What are the options?)**
  - Slow start. Geothermal estimate 30% higher than oil & natural gas
  - HVAC degrading. Congregation wanted proposals to compare vendors and technical options.
  - 2022 Inflation Reduction Act: 40% of project costs covers by federal direct payment.
  - End of 2023 proposals received. Oil & natural gas options were “drop in” component replacement. Geothermal was an integrated design starting from core technical requirements through to a complete HVAC solution.
  - Determined further geothermal design work needed for fixed price proposal – cost: \$120K

# Background information

- 55,000 sq ft building
- HVAC was 30 years old. Two oil fired boilers. One boiler was a 40+ years old steam boiler converted to hot water. 7 roof top units. Past end of economically useful life.
- 50% of the heat was delivered hot water baseboard radiators and cast iron radiators in the sanctuary. No room to install larger air ducts so the geothermal solution is hybrid – both hot water baseboard radiators and forced hot air.
- Some zones were not air conditioned. Geothermal provides A/C to all zones.

# COST COMPARISON: INITIAL OUTLAY



VILLAGE CHURCH  
Congregational · United Church of Christ

Costs	Option 2: Geothermal	Costs	Option 1: heat pump/nat gas
System, gross cost	\$4,674,000	System, gross cost	\$2,143,000
Contingency (3.5%)	\$164,000	Contingency (3.5%)	\$75,000
Interest	\$240,000	Interest	\$68,000
Roof repairs	\$25,000	Roof repairs	—
Rebate: IRA 30%	\$(1,451,000)	Rebate: IRA 30%	—
Rebate: IRA 10%	\$(484,000)	Rebate: IRA 10%	—
Rebate: Mass Save	\$(675,000)	Rebate: Mass Save	\$(80,000)
TBD	—	TBD	—
TBD	—	TBD	—
<b>NET</b>	<b>\$2,493,000</b>	<b>NET</b>	<b>\$2,206,000</b>

## Notes:


- Quotes from GreenerU are stipulated sum (fixed)
- Pricing has been developed based on significant engineering effort to date
- There is some uncertainty as to IRA rebates due to the current political climate




# TOTAL COST OF OWNERSHIP



VILLAGE CHURCH  
Congregational · United Church of Christ



# SYSTEM COMPARISON: EMISSIONS



# EMPOWERING THE FUTURE: FIVE CATEGORIES



VILLAGE CHURCH  
Congregational · United Church of Christ

CREATE AN ENDOWMENT  
FOR CHILDREN  
AND YOUTH MINISTRY



REPLACE AND  
MODERNIZE  
THE HVAC SYSTEM



EXPAND COMMUNITY  
OUTREACH INCLUDING  
VILLAGE TABLE



SECURE THE  
PROPERTY RESERVE



GREEN THE WESTON  
CAMPUS (SOLAR,  
INSULATED ROOF)




# Decision process part 2 (fall 2024 – what option do we choose?)

- Sept: Estimates for natural gas options (boilers and air source heat pumps), oil option, and geothermal all equal at about \$3M with federal direct payments & MassSave rebate.
- Geothermal involved a complete integrated design of all components. Natural gas and ASHP solutions were much more limited “drop in” component replacement.
- Sept – Nov: Weekly church council meetings and extensive engagement with the congregation.
- Dec 10 – congregation (85%) votes for geothermal option
- First production well drilled in December to verify hydrographic data and give the project “substantial start” in CY 2024.


# Thoughts on the decision process

- This was a 10-year journey for our church.
- When the focus shifted to geothermal, it took two years and \$150,000 to reach a decision by the congregation.
- Project costs rose during 3-year decision cycle from an initial estimate of \$1.7M to \$3M due to more detailed design work, expansion of scope, and rising costs.
- Single source to our prime contractor would have saved 10% cost at least and a year of time, but that type of decision was not possible in a congregational church. Comparative bids and technologies were required.
- WVC would not have decided for geothermal were it not for the federal IRA direct payments (40% of project cost) and the MassSave rebate (\$665,000).
- It was not a unanimous decision (85% = yes). Some members still had reservations.



# Wellfield


- 18 wells, each 850 feet deep
- Closed loop = 1 1/2 inch pipes up and down each well
- Wells are filled with cement grout
- Approximately 25 feet of overburden, 825 feet of bedrock
- Over 6 miles of piping
- Field is divided into two 9 well sections to feed into the building.
- Located under the driveway. Nothing is visible on the surface.



## Heating mode:


Heat pumps heat the loop from warm ground water. This sends hot water to the coils in the air handling units and to the baseboard radiators.

- The radiators are always the initial source of heat to a room or space. Air from the Air Handling Units (AHU) supplement the heat from the radiators.
- Radiators provide heat to 47 rooms and spaces each with individual controls.
- The AHU's provide fresh air, heating, & cooling to seven zones. CO2 is monitored in each space to ensure enough fresh air is provided.
- Two of the seven zones service the offices and classrooms. These zones have Variable Air Volume (VAV) units that can heat the air and change the volume of air going to individual rooms to control individual room temperatures. There are 18 VAV's.



## Free Cooling mode:

Chilled water comes directly from the well field. The heat pumps and radiators are not used – dramatically reducing heating costs. Heat pumps can be used near the end of the summer during peak cooling loads.



## Heating & Cooling mode:

Heat pumps provide hot water to the baseboard radiators and chilled water to the AHU's. Used in spring & fall when part of the building is hot and part is cold. Heat is "moved" from the cooling air to the radiators.

The "outside air economizer" mode is used when one zone needs cooling (e.g. the sanctuary for a service) and the rest of the building needs heating. This mode increase the air flow to the space to cool it.



**VILLAGE CHURCH**  
Congregational - United Church of Christ



Home



Alerts



Schedules



Charts



Notes



Users



Weather



Reports



Back



Forward



Logoff



47 °F



40 %RH

18-Nov-25 2:48 PM EST

**EDGE**  
AUTOMATION

Quick View

Advanced

Operation

Points

Setpoints &  
Parameters


Fan Info

Zone Damper  
Settings

Co2 Info

Unit Alarms

## AHU 2 Advanced



**Outside Air**

Damper: 5.0 %  
OA Filter Diff Press: 0.1 in/wc  
Dirty Filter Alarm: Clean

**Mixed Air**

Temperature: 62.8 °F

**Dual Temp**

Valve Upper: 100.0 %  
Valve Lower: 100.0 %  
Cond. Pan Switch Status: Normal  
Freezestat Status: Alarm

**Supply**

Fan Cmd: On  
Fan 1 Status: On  
Fan 2 Status: On  
Fan 3 Status: On  
Fan 4 Status: On

**Supply**

Fan Speed: 43.4 %  
Static: 0.4 in/wc  
 Show Fan Info

**Supply**

Air Temp: 105.6 °F  
Air Humidity: 0.1 %RH  
Smoke Status: Normal  
High Static: Normal  
Supply Flow: 8302.1 cfm

System Reset:  
Auto




**Ground Water Source Heat Pump**

System Mode: Heat Only  
Alarm: Normal  
Run Percentage: 29.35




**Ground Water Loop**

Supply Temp: 46.5 °F




**Dual Temp Loop**

Effective Water Setpoint: 42.0 °F  
Dual Temp Supply Temp: 106.0 °F



**Hot Water Loop**

Effective Water Setpoint: 110.0 °F  
Hot Water Supply Temp: 106.0 °F





Home



Alerts



Schedules



Charts



Notes



Users



Weather



Reports



Back



Forward



Logoff



46 °F



40 %RH

System Mode: Heat Only

# WSHP Advanced

Quick View

Advanced

Points

Pump Information

Operation

Setpoints & Parameters

Heat Pump Information

BTU Meter Information

Glycol Alarm: 0.0 %

Refrigerant Level: 4 ppm

Minimum Flow Valve:  
100.0 %

### Dual Temp

Supply Temperature: 106.0 °F  
Return Temperature: 101.9 °F  
Energy Rate: 383488.06 BTU/hr  
Flow: 81.84 gal/min  
Pressure: 3.68 psi

### Pump 2A

Command: On  
Speed: 100.0 %  
Status: On  
Alarm: Normal  
Lead Pump: Pump2ALead

### Pump 2B

Command: Off  
Speed: 20.0 %  
Status: Off  
Alarm: Normal

### Bypass Valve

Command: Closed  
Valve 1 Status: Closed  
Valve 2 Status: Closed  
Free Cooling: Active

### Chillmaster Heat Pump

System Mode: Heat Only  
System Status: Operational  
Command: On  
Alarm: Normal  
Alarm Indicator: Normal  
Run Percentage: 29.35  
Shutdown Switch: Off  
Dual Temp Supply: 106.0 °F  
Dual Temp Return: 101.9 °F  
Hot Water Supply: 106.0 °F  
Hot Water Return: 105.0 °F

### Ground Water

Supply Temp: 46.5 °F  
Energy Rate: 383488.06 BTU/hr  
Return Temp: 45.6 °F  
Flow: 258.72 gal/min

From Ground

To Ground

P-3A

P-3B

Minimum Flow Valve:  
0.0 %

### Pump 3A

Command: On  
Speed: 100.0 %  
Status: On  
Alarm: Normal  
Lead Pump: PumpP3ALead

### Pump 3B

Command: On  
Speed: 100.0 %  
Status: Off  
Alarm: Normal

Changeover Valve Position:  
Hot Water

To AHU1 & AHU2

From AHU1 & AHU2

From Building

To Building

P-1A

P-1B

### Hot Water

Supply Temperature: 106.0 °F  
Return Temperature: 105.0 °F  
Energy Rate: 60543.88 BTU/hr  
Flow: 96.77 gal/min  
Pressure: 0.06 psi

### Pump 1A


Command: On  
Speed: 100.0 %  
Status: On  
Alarm: Normal  
Lead Pump: PumpP1ALead

### Pump 1B

Command: Off  
Speed: 20.0 %  
Status: Off  
Alarm: Normal

## Geothermal heat pump units


- **3 cabinets with 2 heat pumps in each for a total of 6.**
- **Any of the 6 units can be serviced or replaced while the others are operating.**
- **On the coldest winter day, 3 pumps can maintain the temperature at setpoint in the building. More pumps operate in order to heat the building up from the night setback temperature.**





- 1st Floor A
- 1st Floor B
- FloorPlanHome

## First Floor Plan



# Observations/lessons

- Incorporate an allowance for unforeseen items – we had a leaking roof that required major repairs.
- Investing in design work before contract award allowed for a fixed price contract. Fixed price gave the congregation peace of mind.
- In our retrofit scenario, it took over 3 months after the geothermal system started operating to shake out issues with legacy equipment and “groom” the operation of the new building management system. We had many legacy radiator control valves, thermostats, and air handling components that no longer worked properly. These all needed to be fixed before we could complete balancing of the air distribution and get all rooms operating at the desired temperature. This was also a significant cost.
- Our choice of GreenerU as the prime contractor was one of the best choices we made in the whole project.



<https://wellesleyvillagechurch.org/empoweringthefuture/>